







पिपरी चिंचवड महानगरपालिका, पिपरी - १८
स्थापत्य उद्यान व क्रीडा विभाग
कोटेशन नोटीस स्थापत्य क्रीडा ४११/ २०२४-२५

पिपरी चिंचवड महानगरपालिकेच्या स्थापत्य क्रीडा विभागामार्फत पि. चि. मनपा मधील पिपळे सांदागर येथील श्वान उद्यानात खालील प्रमाणे मागवलेल्या बाबी नमूद अटीनुसार दर देणेकामी त्या क्षेत्रातील अनुभवी पुरवठा धारक अथवा काम करणाऱ्या संस्थेकडून दि. १२/०५/२०२४ ते दि. २२/०५/२०२४ दु. ३.०० वाजेपर्यंत स्थापत्य क्रीडा विभाग, पिपरी चिंचवड महानगरपालिका, पिपरी - १८ येथे सादर करावेत.

- सिलबंद कोटेशन पाकिटावर कोटेशन नोटीस क्र. कामाचे नाव तसेच फार्म / कंपनीचा नावाचा स्पष्ट उल्लेख करावा
- अटीयुक्त, उशिरा आलेल्या व अपूर्ण कोटेशनचा विचार केला जाणार नाही.
- सदर ची कोटेशन नोटीस www.pcmcindia.gov.in या वेबसाइट वर पाहण्यास उपलब्ध आहे
- सदर कामाबाबतच्या अटी शर्ती मनपाकडे मजूर Expression Of Intrest प्रमाणे असतील.
- अधिक माहिती साठी उप अभियंता श्री. लक्ष्मीकांत कोल्हे मो. (9922501767) यांचेशी संपर्क साधावा.

Sr. No	Discreption	Reference image	Unit	Rate Without GST
1	Providing and fixing of 'Jumping Bar' equipment to dimensions as specified: 2.69m L, 0.15m B, 0.63m H. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 15mm HPL and high density polyethene boards/ polypropylene. with vertical posts of 95x95mm in Laminated Scandinavian machine strength graded pine wood treated in autoclave, IV risk class. All joints to be in Stainless Steel finish S-235, AISI-304 and aluminium EN AW 5754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.		per no	
2	Providing and fixing of 'Pause Table' equipment to dimensions as specified. 2 sets of tables of sizes 3.13 m L x 0.83m H and 3.13m L x 0.53 m H required. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 10mm HPL 15 mm high density polyethene boards and 21 mm non-slipping plywood board, plastic parts in Polyethene and polypropylene with vertical posts of 95x95mm in Laminated lasur treated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. Stringers in Laminated lasur treated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. All joints to be in Stainless Steel finish S-235, AISI-304 and aluminium EN AW 5754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.		per no	
3	Providing and fixing of 'A-Frame' equipment to dimensions as specified: 1.86m L, 0.90m W, 0.95m H. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 10mm HPL 15 mm high density polyethene boards, plastic parts in Polyethene and polypropylene with vertical posts of 190x95mm in Laminated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. Stringers in Laminated lasur treated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. All joints to be in Stainless Steel finish S-235, AISI-304 and aluminium EN AW 5754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.		per no	
4	Providing and fixing of 'Dog Walk' equipment to dimensions as specified: 3.60m L, 0.45m W, 0.60m H. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 10mm HPL 15 mm high density polyethene boards, plastic parts in Polyethene and polypropylene with vertical posts of 95x45mm in Laminated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. Stringers in Laminated lasur treated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. All joints to be in Stainless Steel finish S-235, 8.8 DIN267 AISI-304 and aluminium EN AW 5754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.		per no	

Sr. No	Discription	Reference image	Unit	Rate Without GST
5	Providing and fixing of 'Tire Jump' equipment to dimensions as specified. 1.57m L, 0.11m W, 1.37m H. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 10 mm HPL, 15 and 20 mm high density polyethene boards, plastic parts in Polyethene and polypropylene with vertical posts of 95x95mm in Laminated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. All joints to be in Stainless Steel finish S-235, 8.8 DIN267 AISI-304 AISI-316 and aluminium EN AW S754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.		per no	
6	Providing and fixing of 'Dog Tunnel' equipment to dimensions as specified 1.20m L, 0.89m W, 0.67m H. The product to match the colors, design, size, contours and aesthetics exactly as per the image attached. The product to be made in 10mm HPL 15 mm high density polyethene boards, plastic parts in Polyethene and polypropylene with vertical posts of 95x95mm in Laminated scandinavian machine strength graded pine wood treated in autoclave, IV risk class. Stringers in Laminated lasur treated scandinavian machine strength graded pine wood treated in autoclave, IV risk class 95x45mm. All joints to be in Stainless Steel finish S-235, 8.8 DIN267 AISI-304 and aluminium EN AW S754-H111, with robotic welding. All components designed and manufactured to meet with EN 1176 safety standards.			

पिपरी चिचवड महानगरपालिका, पिपरी - १८

स्थापत्य उदयान व क्रीडा विभाग

जा.क्र.स्था.उ./कावि/१५५/२०२४ दि.१०/१०/२०२४



कुर्सेकारी अभियंता
स्थापत्य उदयान व क्रीडा विभाग
पिपरी चिचवड महानगरपालिका,
पिपरी - १८

प्रत. १) ई गव्हर्नेन्स विभाग, वेबसाइट वॉर प्रसिद्धीकमी

२) नोटीस बोर्डे स्थापत्य मुख्यालय - प्रसिद्धीकमी

Note - The Required Site Visit/ inspection shall be carried out by vendor / supplier , before providing the Techno - commercial offer only informative assistance shall be provided by PCMC officials